



# PROJECT UPDATE

## WTP - BROOK STREET PIPELINE

### DUN TRACK CLOSURES

Track closures are now in place for the Codgers Trail and lower Brook Stream track between Blick Terrace and the Whakatu Riding for the Disabled (RDA).

Codgers Trail has been widened to allow machinery access along the route of the new pipeline. Entry to these tracks is strictly prohibited while this work is being done. There are many hazards present during and after work hours. Closures should span four weeks (weather dependant) as the pipeline is built.

#### Current track closures:



- Track Closure
- Construction traffic 5kph limit in place (road trucks/utes and 3rd party vehicles)
- Proposed/Existing cycle and foot traffic routes

### PIPELAYING UNDERWAY

The pipe laying has now started and members of the public may have noticed the new pipe being tracked along the Codgers Trail by a 33 tonne excavator over the past two weeks. A total of 80m has now been laid along one of the most challenging inclines of the project. The pipeline will now progress back along the Codgers Trail toward Brook Street on flatter ground over the next two to three weeks. Photo of pipe being transported along Codgers Trail:



Project Progress:

12% of the way there!



Current Phase:

Pipe Laying



Find Out more:

[www.nelson.govt.nz](http://www.nelson.govt.nz)

### CONSTRUCTION FACTS

Unlike plastic pipelines with socket joints, the concrete lined steel pipe used for this project is welded together. For construction to proceed, a specialist welder from the North Island will call Nelson home for the duration of the project undertaking all the welding required. Welding each joint (internally and externally) takes approximately 2.5 hours and includes preparation, welding, pressure testing, concrete mortar lining and external wrapping of the pipe before the next pipe can be laid.

#### Delivered by:



### CODGERS TRACK WIDENING

To allow access for construction machinery, the current Codgers Trail was widened by approximately 2 metres. Once construction is complete, the track will be reinstated to its original condition and width.

#### Photos from Codgers:

